
Paris Summary Part 2 and Status of UK Electronics/DAQ

Paul Dauncey

Imperial College London, UK

Paris Meeting Part 2

Rest of talks at Paris:

- **Very Front End (VFE) electronics**
 - Christophe de la Taille, Julien Fleury
- **UK electronics/DAQ**
 - Adam Baird, Paul Dauncey
- **Simulation studies**
 - Nigel Watson
- **Organisation**
 - Jean Claude Brient, Sandrine Le Quellec

Will summarise these in (apparently) random order


- Except simulation work was all from UK so is covered in some detail later today

Organisation

- **Medium term** aim for ECAL is beam test at DESY
 - This is currently assumed to be around **Aug 2004**
 - Requires mechanical construction of ECAL to start in **Mar 2004**
 - Competition! SLAC/Oregon are now proposing full Si-W ECAL prototype also; their timescale is end 2005
- **Longer term** aim for ECAL+HCAL(s) is beam test at FNAL
 - Less certain timescale; could be **end of 2004** but could easily slip into 2005
 - Will need to write proposal for beam time (discussion at end of day)
 - Will also help “lock-in” US DHCAL collaborators
- **Documentation**
 - Want central repository of “all” documentation (not clear exactly what)
 - Have set up an **EDMS** (CERN) database at Ecole Polytechnique
 - Web accessible interface but not email list handler
 - Somewhat overly complicated for our needs?



VFE overview

- **Very Front End (VFE)** electronics is what the UK connects to
 - **VFE PCB** physically holds the silicon wafers and VFE readout electronics
 - Main component of VFE readout electronics is the **VFE ASIC**, FLCPHY2
 - Three flavours of VFE board, with either **216 or 108 channels**, 12 or 6 chips






VFE chip status (de la Taille)

- FLCPHY2 is **second iteration** of design
- Small fabrication run completed in **Jul 2003**
- Testing now ~complete




VFE chip performance

- Chip performs to **requirements**
 - Pedestals; rms 5mV (in 1.4V)
 - Peaking time; rms 1ns (on 180ns)
 - Crosstalk; <1%
- Will go to **full production** ~now
 - Need ~600 chips
 - Back **end Dec**, test in Jan



VFE board status (Fleury)


- Prototype PCB was **half-size**
 - Scaling up to full number of channels
 - Several changes to UK interface; still in flux




- Trying to freeze **final design** ~now
 - Big jump from prototype, so doing production in two steps
 - Will produce two pre-production PCBs by end **Oct 2003**
 - Ideally test these and then make the other ~60 needed during **Dec 2003**
 - But **must** test with UK prototype before this; delay by ~one month
 - VFE PCB is part of ECAL mechanical structure; **UK delaying assembly!**

Overview of UK electronics

- Need to produce six **readout boards** for whole ECAL
 - **1728 channels** maximum per board, 9720 channels total
- All other items needed for readout commercially available
 - Crate, PC, VME interface, cables
- Board architecture
 - Eight **Front Ends** (FE), each controlling one or two VFE PCBs
 - Single **Back End** (BE) does data fan in/out to FEs
 - Based on **CMS FED** board




CMS FED board (Rob Halsall, RAL)




CALICE board layout (Adam Baird, RAL)

- Design and layout “close” to completion
 - Six months later than scheduled
 - Unfortunately, these became too closely coupled
 - Aiming to send for fabrication within two weeks




CALICE board FE layout

- Main change from CMS is **FE area**
 - Higher component count in CALICE so denser layout



Readout board firmware


- Also need to write **firmware** (code to load into FPGAs)
 - VME interface **identical** to CMS; (we hope) no work needed
 - BE close but not identical so some work needed (Dave Mercer, Manc). Will also contain VME **trigger interface**, not existing in CMS (Matt Warren, UCL)
 - FE completely different; effectively a **new design** (Osman Zorba, IC)
- Progress being made in these areas using simulation
 - But real prototype CALICE board will speed things up



- E.g. FE trigger delay simulation
 - Allows adjustment in **3ns** steps so trigger arrives at time of VFE chip peak


DAQ software overview

- **Multi-PC** system driven by common run control PC
 - Each PC is **independent**; can have separate technology (VME, PCI, CAMAC, etc)
 - PC **configuration** can be changed easily; single VME crate readout for separate system tests possible.
 - **Multiple** tasks could be run on one PC; e.g. run control, ECAL and event build
- Prefer PCs **outside** radiation area if possible
- Have own hub and network (cost?) or rely on network infrastructure at beam line?



DAQ topology

- For tests, assume **worst** case; each subsystem (ECAL, HCAL, beam monitoring and slow controls) read out with **separate** PC
 - Require one socket-socket branch for each



- Each branch can read out **separate** technology (VME, PCI, etc)
- **Monitor** does not necessarily sample all events; its buffer allows through events only when **spare CPU** available

DAQ status

- First version of data **structure** software exists
 - Records and subrecords; loading/unloading, etc.
 - Arbitrary payload (templated) for subrecords
- First version of data **transport** software exists
 - Buffers, copiers, mergers, demergers, etc.
 - Arbitrary payload (templated) with specialisation for records
- First version of **run control** software exists
 - Both automatic (pre-defined) and manual run structures
- **VME** hardware access working
 - SBS 620 VME-PCI interface board installed in borrowed VME crate
 - Using Hardware Access Library (CERN/CMS)
- These work together
 - Sustained rates achieved depend critically on PCs, network between the PCs on the different branches, compiler optimisation, inlining, etc; a lot of **tuning** needed

DAQ alternatives: MIDAS? XDAQ?

- **MIDAS** (PSI)
 - No experience of using this in UK
 - Written for ~MByte data rates, ~100 Hz event rates, single PC systems
 - Limited state diagram; no ability to take different types of events in run
 - A lot of baggage (databases, slow controls); more complex than required
 - C, not C++, so less natural interface downstream (and not type-safe)
- **XDAQ** (CERN/CMS)
 - Significant experience of this in Imperial; useful to have experts on hand
 - Optimised for CMS; no beam spill structure and asynchronous trigger and readout but easily deals with CALICE event rates and data sizes
 - Includes HAL automatically so (should be) simple to retrofit later
 - Deserves further investigation
- If moving to an existing system, XDAQ seems more suitable (?)
 - Beware of “**3am crash**” issue; it is hard to debug code written by other people in a hurry...

Electronics schedule

		2003												2004							
		J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A
Prototype 2 boards	Design	█	█	█																	
	Layout		█	█	█	█	█	█	█	█											
	Fabrication and assembly				█						█										
	Testing					█	█	█	█	█	█	█	█	█	█	█	█	█			
	VFE PCB tests							█					█								
Production 9 boards	Redesign									█	█				█	█					
	Layout											█					█				
	Fabrication and assembly												█					█			
	Testing, including Paris system cosmic tests													█	█	█			█	█	
	DESY beam test																				█

Board cost estimates (£k)

		Original	Current
Prototype	NRE	2.5	3.0
(2 boards)	Components	8.0	7.8
	Fabrication	1.0	1.5
	Assembly	5.0	6.0
Production	NRE	2.5	3.0
(9 boards)	Components	35.0	35.1
	Fabrication	4.5	6.5
	Assembly	13.5	22.5
Total		72.0	85.4

N.B. fab/ass cost **not final** until board design and layout complete

Possible savings from rest of budget

- Electronic boards were the **major item** but not total budget
 - Miscellaneous other electronics; **£2k**
 - Custom cables (100 needed); **£15k**
 - PC, disk, VME interface, VME crate; **£4k, £8k, £4k, £6k**
- Major saving in **cables**
 - VFE PCB will use same connector as readout board; don't need custom
 - Number of VFE PCBs (and hence cables) reduced from doubling PCB size
 - Off-the-shelf cables (70 needed); **£6k**
- Minor savings **elsewhere**
 - VME interface, VME crate; **£3k, £5k**
- Within a **few £k** of budget
 - Under-using travel so could transfer from there if necessary

Summary

- There is **progress** in CALICE as a whole
 - Mechanics and electronics converging early next year
 - Aiming for DESY beam test in Aug 2004
- UK electronics going **slowly**
 - Six months behind schedule
 - Now critical path for ECAL as a whole
 - Also cost estimated to be going over budget
- Not gone **critical** (yet...)
 - After VFE test in Jan 2004, will disconnect from mechanical ECAL assembly, giving a little breathing space
 - Next date to aim for is system test in Jul 2004
 - Cost overrun can probably be gained back from other sources